OFFICE OF THE SUPERINTENDING ENGINEER, ELECTRICAL DEPARTMENT, BANGALORE.

Notification dated the 13th July 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, up to 1 P.M. on the 8th August 1938 for constructing one block of Operator's quarters, one block of Linemen's quarters and two blocks of latrines at Dodballapur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of October 1938.

2. The plans, detailed estimates and conditions may be seen at the Office of the Superintending Engineer, Electrical Department, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 350 in cash or Government Promissory notes, as earnest money, and be superscribed "Tender for constructing Electrical Buildings at Dodballapur", in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be pasted on the notice board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Chief Electrical Engineer will be final and legally binding.

Abstract of the estimate of the probable cost of constructing Operator's Quarters at Dodballapur.

Serial No.	Items of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		Rs.
1	Earthwork excavation for foundations, etc.	C.yd.	0 3 3	53	
2	Stone jelly concrete in chunam mortar	C.ft.	0 3 6	596	
3	Size stone in mud for foundations and basement with bond stones in every course, as per specifications	,,	0 3 6	1,031	
4	Burnt brick in clay superstructure	,,	0 3 6	2,097	
5	Burnt brick in lime mortar superstructure	,,	0 4 0	519	
6	Burnt stone slabs 6" thick roughly dressed and fixed	S.ft.	0 6 0	415	
7	Pointing with cement mortar	Sqr.	3 4 0	1.53	
8	Chunam plastering, 2 coats	,,	3 0 0	55.43	
9	White and colour-washing, two coats	,,	0 4 6	56.96	
10	Plain cornice 9" thick all round front verandah	R.ft.	0 8 0	61	
11	Brick in mortar parapet wall all round, as per design.	,,	0 12 0	58	
12	Flooring with 1" cement concrete over 3" chunam concrete, including cement plastering	Sqr.	20 0 0	8.14	
13	Roofing with first class Mangalore tiles on T. W. reepers 2"×1" including wood oiling to reepers	,,	26 0 0	12.21	
14	Ridge tiles set in mortar and cement pointed	R.ft.	0 8 0	75	
15	Terrace with R. C. concrete 4" thick with brick kappi concrete and 2 coats of flat tiles set in mortar and plastered both top and bottom including centering, etc., complete	Sqr.	60 0 0	3.70	
16	Plain teak wood eaveboard 9" deep including fixing.	R.ft.	0 6 0	149	
17	Teakwood wrought and put up including wood oiling, two coats	C.ft.	5 8 0	76.58	
18	Doors, T. W. frames and battened shutters, 1" thick, with hinges, clamps, etc., complete as per drawing.	S.ft.	1 6 0	319	
19	T. W. windows with battened shutters 1" thick and iron bars, hinges, hooks, eyes and clamps, etc., as per drawing	S.ft.	1 10 0	96	
20	Teakwood cup-board with ¾" thick battened shutters and teakwood planks and shelves as per drawing.	,,	1 4 0	96	
21	Rolled steel girders in front of verandah	Cwt.	14 0 0	6.40	

Serial No.	Item of work	Unit	Rate	Quantity	Rates to be quoted
22	Expanded metal 3″×1½″ mesh with ⅛″ thick strands T. W. frames with panelled doors, etc., complete, as per design	S.ft.	0 10 0	112	
23	Chocolate painting, 2 coats	Sqr.	3 8 0	13.57	
24	Ventilating tiles, fixed comp.	No.	2 0 0	8	
25	Constructing sinks	No.	5 0 0	2	
26	Stone mortar and pestle	No.	5 0 0	2	
27	Chunam borders at ends	R.ft.	0 3 0	22	
28	G. I. down-water pipes of plain G. I. sheet 3″ dia.	No.	0 6 0	6	
29	Constructing chimneys in bath room, as per design	No.	15 0 0	1	

Abstract of the estimate of the probable cost of constructing Quarters for 4 coolies at Dodballapur.

Serial No.	Items of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		Rs.
1	Earthwork excavation and filling in foundation	C.yd.	0 3 3	29	
2	Concrete stone jelly in lime mortar in foundation	C.ft.	0 3 6	309	
3	Stone in clay foundation and basement with bond stones in every course as per specifications	,,	0 3 6	741	
4	Burnt brick in clay superstructure	,,	0 3 6	1,538	
5	Burnt brick in mortar	,,	0 4 0	537	
6	Stone slabs 6″ thick roughly dressed and fixed in mortar	S.ft.	0 6 0	141	
7	Chunam plastering	Sqr.	3 0 0	44.00	
8	Cement plastering with thread lining	,,	3 4 0	1.50	
9	White and colour washing, 2 coats	,,	0 4 6	45.50	
10	Roofing with first class Mangalore tiles on T. W. roopers, 2″×1″ including wood oiling, etc., complete.	,,	26 0 0	15.00	
11	Ridge tiles set in mortar and cement pointed	R.ft.	0 8 0	63	
12	Ventilating tiles fixed comp.	No.	2 0 0	16	
13	T. W. work wrought and put up including 2 coats of wood oiling	C.ft.	5 8 0	52.52	
14	T. W. doors battened 1″ thick, shutters and all fixtures complete including iron clamps 1′ long (as per drawing)	S.ft.	1 6 0	156	
15	T W, battened windows with 1″ thick shutters and ⅝″ dia. iron bars with all fixtures, etc., complete as per drawing	,,	1 10 0	75	
16	Chocolate painting, 2 coats	Sqr.	3 8 0	5.50	
17	Constructing sinks, comp.	No.	5 0 0	4	
18	Providing mortar and pestle fixed complete	,,	5 0 0	4	
19	Flooring with 3″ lime concrete, 1″ cement concrete, and ½″ thick cement plastor, etc., complete	Sqr.	20 0 0	8.00	

Abstract of the estimate of the probable cost of constructing one unit of Latrine at Dodballapur.

Serial No.	Items of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		Rs.
1	Earthwork excavation for foundation and filling in basement	C.yd.	0 3 3	4	
2	Stone in lime mortar foundation and basement	C.ft.	0 4 6	130	
3	Burnt brick in lime mortar superstructure	,,	0 4 0	193	
4	Chunam plastering	Sqr.	3 0 0	4.91	
5	Cement pointing with thread lines	,,	3 4 0	0.56	
6	White and colour-washing, 2 coats	,,	0 4 6	5.47	
7	Cement plastering ½″ thick	,,	10 0 0	0.80	
8	Tar washing, 2 coats	,,	2 0 0	0.63	
9	Flooring with 3″ concrete and 1″ cement concrete and ½″ cement plaster	,,	20 0 0	0.38	
10	Fixing outlets and constructing drains, etc.	L.S.	10 0 0		
11	Providing galvanised iron sheet tubs 12″×6″ complete with tarring	No.	0 12 0	6	